



# SHAW ELECTRIC, INC.

## GREENHILL POINT APARTMENTS WATERLOO, IA

Specialty Construction:

Green Building/LEED Project | (\$500,000 - \$2 Million)



**Size of Project:**  
47 Unit Apartment Building



**Length of Project:**  
11 Months

### ***TYPE OF CONSTRUCTION***

Shaw Electric was awarded a project on a new apartment building in Waterloo, Iowa. The Shaw team was able to save the owner money by reducing labor costs on the project by utilizing prefabrication of the apartment units and building them in house in the prefab shop in Davenport.

### ***BUILDING FEATURES***

The work Shaw completed on this new construction project included the design of the complete electrical and fire alarm systems for the 47-unit apartment building. They furnished and installed three phase 1,200 Amp electrical service meter banks with 125 amp and 150 amp single phase apartment feeders and 400A three-phase house panel, electric heat throughout the building, parking lot lighting and utilized Energy Star compliant materials and methods.